

CostWORX is the leading wholesale distributor of telecom & technology infrastructure products, supplying globally through a network of local alliance partners.



## 55m Guyed Mast - 15m<sup>2</sup> Loading

Optimised for cellular telecom applications, this structure is produced with deployment and operation in mind and is capable of supporting 15m<sup>2</sup> of antenna load whilst remaining within a deflection limit of 0.5° at operational wind speed.

Produced from premium steel members hot dip galvanised equivalent to ASTM A123 (2000) and connected with high grade galvanised bolts, this structure has a design life in excess of 25 years.

Export packed and supplied with guy furniture, holding down bolts, anchor plates and setting template this product is the quality choice.

Loading	Height	Туре	Area
Distributed	Over Top 10m	Antenna Loading	15m²
Linear	Vertical Run	Feeder Cable & Ladder	0.40m²/m

Design Wind Speeds (3 Second Gust)	
Basic Wind Speed	38.0 m/s
Operational Wind Speed	37.0 m/s

Deflection	
Less than or Equal to	0.5° (at Operational Wind Speed)

Design Parameter	
Structure Class	2
Exposure Category	C
Topographic Category	1

## **Design Standards**

Material	Standard	Steel Grade	Tensile Strength	Yield Strength
Structural Steel	JIS G 3444	STK 41	402 N/mm <sup>2</sup>	235 N/mm <sup>2</sup>
	ASTM A 53-87	Grade A	331 N/mm <sup>2</sup>	207 N/mm <sup>2</sup>
Structural Bolts	BS 3692	8.8	830 N/mm <sup>2</sup>	664 N/mm²



CostWORX is the leading wholesale distributor of telecom & technology infrastructure products, supplying globally through a network of local alliance partners.

## **Codes of Practice**

ANSI/TIA 222-G : 2005 - Structural Standard for Steel Antenna Tower and Antenna Support Structures

ANSI/AISC 360-05 : 2005 - Specification for Structural Steel Buildings

Galvanization Equivalent to ASTM A123 (2000)

Features		
- Guy Wires and Furniture		
- Work Platform	5m Below Top	
- Rest Platform	20.2m / 31.8m / 43.3m	
- Holding Down Bolt Kit		
- Setting Template		
- Lightning Spike		